13. CONDUITS SHALL ENTER THE BOX WITH MANUFACTURED LONG RADII TYPE OR STANDARD 45° ELBOW.
14. FACTORY BOTTOM WITH 2" DRAIN HOLE IS ACCEPTABLE IN LIEU OF GROUTED BOTTOM AND ROOFING PAPER.
15. PULL BOX SHALL BE SIZE #3 1/2 MIN. UNLESS SHOWN OTHERWISE ON PLANS OR REQUIRED.
16. PULL BOXES SHALL BE PLACED AT INTERVALS NOT EXCEEDING 200 FEET IN CONDUIT RUNS.
17. INSTALL PULL BOX EXTENSION(S) AS REQUIRED TO SET TOP OF PULL BOX FLUSH WITH SURROUNDING GRADE.

APPROVED BY			DRAWING NO.
DATE 3/3/92	CONCRETE PULLBOX NOTES – CONTINUED	CITY OF SAN JOSE CALIFORNIA	E–06
	DEPARTMENT OF PUBLIC WORKS		