STANDARD NOTES

- **AB** ABANDON. IF APPLIED TO CONDUIT, REMOVE CONDUCTORS.
- **BC** INSTALL PULL BOX IN EXISTING CONDUIT RUN.
- **CB** INSTALL CONDUIT INTO EXISTING PULL BOX.
- **CC** CONNECT NEW AND EXISTING CONDUIT. REMOVE EXISTING CONDUCTORS AND INSTALL CONDUCTORS AS INDICATED.
- **CF** CONDUIT TO REMAIN FOR FUTURE USE. REMOVE CONDUCTORS. INSTALL PULL WIRE OR ROPE.
- **DH** DETECTOR HANDHOLE. TYPE A, UNLESS OTHERWISE SPECIFIED.
- **PEC** PHOTOELECTRIC CONTROL.
- **RL** RELOCATE EQUIPMENT.
- **RR** REMOVE AND REUSE EQUIPMENT.
- **RS** REMOVE AND SALVAGE EQUIPMENT.
- **SC** SPLICE NEW TO EXISTING CONDUCTORS.
- **TSP** TELEPHONE SERVICE POINT.
- **RI** REMOVE EXISTING CONDUCTORS. INSTALL NEW CONDUCTORS AS INDICATED.

ABBREVIATIONS

C	SUPPLIED AND INSTALLED BY CONTRACTOR, UNLESS SPECIFIED OTHERWISE.
CSJ	INSTALLED BY CITY
DLC	LOOP DETECTOR LEAD IN CABLE
E	EXISTING TO REMAIN
EMS	EXTINGUISHABLE MESSAGE SIGN
FB	FLASHING BEACON
HPS	HIGH PRESSURE SODIUM
COM	TRAFFIC SIGNAL COMMUNICATIONS CABLE
LPS	LOW PRESSURE SODIUM
MT	CONDUIT WITH PULL WIRE OR ROPE
PB	PULL BOX
PEC	PHOTOELECTRIC CONTROL
PED	PEDESTRIAN
PEU	PHOTOELECTRIC UNIT
PPB	PEDESTRIAN PUSH BUTTON
PT	POST TOP
R	REMOVE (TO BECOME PROPERTY OF CONTRACTOR)
SN	SOLID NEUTRAL
S	SALVAGE (DELIVER TO CSJ AS DIRECTED BY THE ENGINEER)
SP	SERVICE POINT
UNO	UNLESS NOTED OTHERWISE
USO	UNLESS SPECIFIED OTHERWISE
WP	WEATHER PROOF
XFMR	TRANSFORMER

APPROVED BY [signature]
DATE 3/3/92

TRAFFIC SIGNAL AND STREETLIGHTING
NOTES AND ABBREVIATIONS

DEPARTMENT OF PUBLIC WORKS

CITY OF SAN JOSE CALIFORNIA

DRAWING NO. E-01a